

ROSENDIN ELECTRIC, INC.

Commercial Electrical Contractors | Texas License: TX-TECL-18042 (TDLR Active)

Austin Office: 10830 Metric Blvd, Austin, TX 78758 | Phone: (512) 835-2400 | estimating@rosendin.com

FORMAL SUBCONTRACT BID PROPOSAL

Project: The Domain Tower B - Class-A Commercial MEP **Date:** September 10, 2026 | **CSI Division:** 26 00 00 - Electrical & Lighting
Location: 11400 Domain Dr, Austin, TX 78758
Submitted To: Apex Commercial General Contractors LLC / Austin Commercial, LP

TOTAL BASE BID LUMP SUM: \$1,225,000.00

(One Million Two Hundred Twenty-Five Thousand Dollars and 00/100)

SCHEDULE OF VALUES (ITEMIZED LINE ITEMS BREAKDOWN):

ITEM #	DESCRIPTION OF WORK	UNIT	STATUS	TOTAL AMOUNT
01	1600A Main Service Switchboard (Square D QED-2, 65kAIC, 480/277V)	LS	INCLUDED	\$380,000.00
02	Step-Down Distribution Dry Transformers (NEMA TP-1 Premium)	LS	INCLUDED	\$145,000.00
03	Copper Feeder & Branch Conduits (ASTM B8 Class B THHN conductors)	LF	INCLUDED	\$290,000.00
04	Penthouse Crane Rigging & Mobile Crane Hoisting to 14th Floor	LS	INCLUDED	\$45,000.00
05	UL 1479 Through-Penetration Firestopping Assemblies	LS	INCLUDED	\$22,000.00
06	Seismic Engineered Structural Bracing per IBC Section 1613	LS	INCLUDED	\$55,000.00
07	Temporary 400A Jobsite Distribution Board Maintenance	LS	INCLUDED	\$18,000.00
08	Architectural Lighting & Dual-Lite Emergency Battery Inverters	LS	INCLUDED	\$170,000.00
09	Testing, Megger Reporting, Energization & 1-Yr Warranty	LS	INCLUDED	\$100,000.00

TOTAL CONTRACT BASE BID SUM: \$1,225,000.00

VALUE ENGINEERING (VE) ALTERNATES PROPOSED

VE-01: Feeder Cable Material Optimization

Furnish ASTM B800 8000-Series Aluminum Alloy MC Feeder Cable in lieu of specified copper conduit runs.
Fully meets NEC 2023 ampacity requirements and saves significant installation labor.

DEDUCT FROM BASE BID: -\$35,000.00

SCOPE INCLUSIONS & ZERO-EXCLUSIONS COMPLIANCE GUARANTEE

- * Crane Hoisting: Full crane mobilization, rigging crew, street closure permits to 14th-floor penthouse included.
- * Firestopping: Complete UL 1479 through-penetration rated sealants and sleeve firestop assemblies included.
- * Seismic Restraints: PE-stamped engineered seismic bracing for all conduits 2.5 in. and larger per IBC Section 1613.
- * Temporary Power: Furnishing and servicing 400A jobsite temporary power distribution panels fully included.
- * Exclusions: ZERO SCOPE EXCLUSIONS. Clean, fully compliant, turnkey commercial trade proposal.

EQUIPMENT LEAD TIMES & COMMERCIAL TERMS

Main Switchgear Lead Time: 10 WEEKS from approved submittal drawings.

Schedule Alignment: Meets and exceeds owner's 12-week equipment delivery milestone (0 weeks penalty).

Commercial Insurance: Travelers ACORD 25 Certificate attached (\$5,000,000 Commercial Umbrella liability).

Payment Terms: AIA Document G702/G703 Monthly Progress Billings; 10% Retainage; Net 30 days.

SUBMITTED & CERTIFIED BY:

David K. Ramirez, CPE

Vice President - Estimating & Preconstruction
Rosendin Electric, Inc. | Texas Electrical Contractor License #18042

ACCEPTED & AGREED TO BY GENERAL CONTRACTOR:

Authorized Signature / Project Executive

Apex Commercial General Contractors LLC

Date: _____